

# Inspections & Maintenance

## North Dakota Stormwater Conference

Minot, ND  
March 28, 2007



**NORTH DAKOTA**  
DEPARTMENT *of* HEALTH

Randy Kowalski  
(701) 328-5239

[rkowalsk@nd.gov](mailto:rkowalsk@nd.gov)

# Getting Started

- ▶ Pre-Inspection Planning
  - Required Frequencies
  - Areas to be inspected
  - Record / Report Requirements
  - Inspector Qualifications
  - Equipment
  - Forms / Checklists
  - Corrective Action Procedure

 CONSTRUCTION STORM WATER  
POLLUTION PREVENTION PLAN  
NORTH DAKOTA DEPARTMENT OF HEALTH  
DIVISION OF WATER QUALITY  
DWR 16386 (2/05)

**NORTH DAKOTA DEPARTMENT OF HEALTH  
NDPDES PROGRAM**

**Construction  
Storm Water Pollution Prevention Plan  
Guidance Forms**

**CONTENTS**  
Use the following information as a checklist for developing the Storm Water Pollution Prevention Plan.

1.  PROJECT DESCRIPTION
2.  SITE MAP DEVELOPMENT
3.  SIGNATORY CERTIFICATION
4.  BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL
5.  OTHER BEST MANAGEMENT PRACTICES
6.  SIGNIFICANT MATERIALS
7.  ADDITIONAL OWNERS/OPERATORS
8.  SITE INSPECTION RECORD

A SWPPP must be prepared and implemented for all construction activities covered under NDR10-0600. A copy of the SWPPP must be submitted to the Dept. of Health for projects that involve 50 or more acres, or have a discharge point located within 2000 ft. of, and flow to, a water body that is listed as impaired due to sediment or parameters associated with sediment transport.

# Inspection Frequencies Differ by Permit

## ▶ **Industrial Facilities**

- 2 Comprehensive per year (minimum)

## ▶ **Construction Sites**

- Once per 2 week plus following rain

## ▶ **Storm sewers serving Cities > 10,000**

(Municipal Separate Storm Sewer Systems MS4s – for short)

- Annual to once in 5 years
  - ▶ (based on structure type)



# Records

Inspection records must contain the following:

- 1) Date and time of the inspection
- 2) Name and qualifications of the inspector
- 3) Major observations relating to the implementation of the SWPP plan
- 4) Corrective actions taken
- 5) Rainfall date and amount for all events  $>1/2$  in
- 6) Updates to SWPP when E/S controls are changed

*Inspection reports kept on file with the BMP plan for at least three (3) years after the date of inspection*



# What Must Be Inspected

- ▶ Overall Housekeeping & Control practices
  - Sediment leaving disturbed areas
  - Material storage secure
- ▶ Discharge points
  - Adjacent properties
  - Surface waters
- ▶ Erosion / Sediment Controls
  - Installed and working correctly
  - Maintenance needed?



# Housekeeping

- ▶ Concrete wash water
  - Must be contained
  - Cannot drain to storm sewer
- ▶ Bulk storage must have adequate leak and spill protection
- ▶ Dewatering or basin draining (e.g., pumped discharges, trench/ditch cuts for drainage) must follow BMPs
  - must be operated to minimize release of sediment
  - include energy dissipation device.



# Equipment Access

Vehicle exit locations must be inspected for sediment tracking onto paved surfaces.

Tracked sediment must be removed from paved surfaces, within 48 hours, or within a shorter time specified by local authority



# Sediment ponds, traps, basins

- ✓ Built as designed
- ✓ Adequate Sediment storage
- ✓ Outlet riser to provide 24hr detention
- ✓ Stabilized emergency overflow
- ✓ Energy dissipation outlet
- ✓ Clean-out required when  $\frac{1}{2}$  full



# Sediment Pond / Basin

Permanent –temporary (circle) sedimentation basins: (location/ID) \_\_\_\_\_

Required basin installed (> 10 acres/ single point (T) or >1 acre new impervious (P))?	Yes	No
Does basin have energy dissipation for outlet?	Yes	No
Stabilized emergency overflow outlet?	Yes	No
Was basin constructed /operational concurrent with construction?	Yes	No
Are slopes stabilized with perma cover or temp erosion protection within 200' of surface water?	Yes	No
Is basin connected to surface waters? Yes      Name/description waters: _____		
Was discharge- connection stabilized within 24 hours of connecting?	Yes	No
Dewatering: Onsite to a temp. settling basin? Yes No    If offsite, is water turbid?	Yes	No
If no settling basin, was appropriate BMPs for turbidity and scour applied?	Yes	No
Is discharge from site creating a nuisance conditions or WQ violations?	Yes	No
Observations:		



Construction Permit Criteria--  
Appendix 1, Page 19

# Down Slope Barriers

## Silt fence

- ▶ Stakes secure & trenched-in
- ▶ J-hook (smile)
- ▶ 1/4ac per 100ft
- ▶ Should not be in channel (unless you need a temp. dam)
- ▶ Sediment Removal needed when 1/3 height



# Infrastructure O&M



24 11:02 AM







# Temporary Erosion Protection

- ▶ Seed & mulch on areas where grading ceased
- ▶ Sufficient amount and anchoring
- ▶ Water and wind erosion protection
- ▶ 21 day time for cover on area within 200ft of water
  - Pond embankments, Ditches, Berms, Soil Stockpiles
  - Does not include clean aggregate, demolition concrete and sand stockpiles





# Stockpiles

Temporary soil stockpiles must have effective sediment controls,

Not placed in waterways

- Curb and gutter systems
- Conduits
- Ditches



# Ditch Stabilization

Are ditches draining water off-site or diverting water around site stabilized within 200 lineal feet of discharge to surface water or adjacent property?

Should be done within 24 hrs of connecting





# Pipe outlets

- ✓ Must have temporary or permanent energy dissipation within 24 hours of connection
- ✓ Proper material per design – expected flow







# Discussion

