

## SWPPP Implementation

Site management, inspections, amendments and corrective actions

2011 North Dakota Storm Water & Pollution Control Conference  
 April 5, 2011  
 Gladstone Inn & Suites, Jamestown ND  
 Dwayne Stenlund, MSc., CPESC  
 Resource Professionals Alliance




### Contractor Quality Control Program

- Ensuring compliance with contractor permit provisions
- Conducting contractor NPDES inspections
- Maintaining a contractor NPDES inspection log
- Incorporating erosion control work into the project
- Mulching/Seeding in a timely manner
- Proper maintenance of devices
- Removal of devices
- A certified erosion control supervisor to conduct program

### Erosion Control Supervisor





- Must be available by phone 24 hrs/day 7 days a week
- Must be knowledgeable (certified) in erosion/sediment control site management
- Must be able to respond to emergency situations at the job site within 12 hrs
- Responsible for implementing **all** the provisions of the storm water pollution prevention plan

### Erosion Control Supervisor

1. Coordinate work of subcontractors.
2. Prepare weekly erosion control schedules.
3. Attend all weekly construction meetings.
4. Prepare the erosion/sediment control site amendment and corrective action plans.
5. Provide erosion/sediment control for contractor's temporary work.
6. Ensure that permits are acquired and complied with for borrow pits, dewatering, temporary work in rivers/streams etc.

### Erosion Control Supervisor Cont.

7. Ensure that erosion/sediment control work is done in a timely manner and meets permit requirements.
8. Ensure project is stabilized prior to suspension of the work.
9. Coordinate with all Federal and State Agencies.
10. Ensure that proper cleanup occurs from vehicle tracking on paved surfaces.
11. Ensure that proper cleanup occurs where sediment leaves the right-of way.



**May 2010**

Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
						1
						Rainfall: _____ in.
Rainfall: _____ in.						
9	10	11	12	13	14	15
Rainfall: _____ in.						
16	17	18	19	20	21	22
Rainfall: _____ in.						
23	24	25	26	27	28	29
Rainfall: _____ in.						
30	31 Memorial Day					
Rainfall: _____ in.	Rainfall: _____ in.					

Installation of road at curbs prevents sediment from running off a site.

**Best Management Practices**  
Best Management Practices (BMPs) are methods to control, prevent, and minimize stormwater pollution. They can include:


- preserving existing vegetation whenever possible
- staging construction sequence to avoid or minimize soil disturbance
- installation of controls like seeding, sodding, soil stabilization, diversions, stream crossings, sediment basins, silt fences, site entrance pads, storm drain inlet protection

The MPCCA manual Protecting Water Quality in Urban Areas available on the MPCCA Web site provides more details on these practices. See page 16 of the permit for more information.


BMP INSPECTION REPORT		THIS REPORT IS VALID ONLY IF THE INSPECTOR HAS REVIEWED THE PROJECT AND VERIFIED COMPLIANCE WITH ALL REQUIREMENTS OF THE PERMIT. THIS REPORT IS NOT VALID IF THE INSPECTOR HAS NOT REVIEWED THE PROJECT AND VERIFIED COMPLIANCE WITH ALL REQUIREMENTS OF THE PERMIT. THIS REPORT IS NOT VALID IF THE INSPECTOR HAS NOT REVIEWED THE PROJECT AND VERIFIED COMPLIANCE WITH ALL REQUIREMENTS OF THE PERMIT. THIS REPORT IS NOT VALID IF THE INSPECTOR HAS NOT REVIEWED THE PROJECT AND VERIFIED COMPLIANCE WITH ALL REQUIREMENTS OF THE PERMIT.
Client: _____ Project name: _____ and Reg. no. _____		<input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> MAYBE <input type="checkbox"/> NOT SURE <input type="checkbox"/> OTHER
Inspected By: _____ Date and Time: _____ Page _____ of _____		
A. Phase of Development: <input type="checkbox"/> Initial Site Grading <input type="checkbox"/> Building and Construction <input type="checkbox"/> Paved Lot		Facility Name: _____ Facility Contact and Title: _____ Facility Street Address: _____ Location Description: _____ City: _____ State: _____ Zip: _____ E-MAIL Address: _____
B. BMP Applied (check all that apply): 1. Construction Erosion Control: _____ 2. Stormwater Management: _____ 3. Sediment Control: _____ 4. Silt Fence: _____ 5. Check Dams: _____ 6. Diversion: _____ 7. Grass Strips: _____ 8. Silt Protection: _____ 9. Outlet Protection: _____ 10. Sediment Basins: _____ 11. Temporary Sealing: _____ 12. Permanent Sealing: _____ 13. Goodwill/Sealing: _____		Mediums of through which the number of disturbed acres which drain through: _____ of Acres: _____ Receiving Water: _____ Detached Acres: _____
C. Additional BMPs used (optional practice and location): _____		Any Discharge Sampling Data Attached: <input type="checkbox"/> Yes <input type="checkbox"/> No If a qualified person under the direct supervision of a QCP conducted, discharge and/or flow measurements, the QCP must be present and the measurements must be taken in accordance with the requirements of the permit. Lack of adherence to the requirements of the permit may result in the permit being suspended or terminated.
D. Additional Comments: _____		I, _____, the QCP, QCI, or a qualified person, certify that the above information is true and correct to the best of my knowledge and belief. I am not aware of any falsification of information, including the possibility of false and unrepresentative data.
E. Sampling: Intermittent sampling necessary to evaluate the effectiveness of BMP implementation based on evaluation of qualified professional. Yes _____ No _____		Signature: _____ Date: _____ Responsible owner/operator: _____ Date: _____ Signature: _____ Date: _____



## Build a form



Item/Location	Description/Task	Date	Correction Schedule Date	Status



**ESC INSPECTION REPORT**

Report No. 14  
START - Sta. 435  
Valley View Road

EDEN PRAIRIE

LOG

Item #	Description/Task	Date	Schedule	Status
W11-01	Sta. 400 - 420 Stabilize exposed soil 10-21-04 Not completed. Stabilize median areas. 10-28-04 1500' required within 7 days of completed grading operations. Area currently being worked.	10-14-04	11/9	Open
W11-01	11-11-04 Check all areas of finished stabilization. If not stable as resolved using Cut 3 in ditch bottoms and Cut 1 for slopes only. Edge of temporary pavement should be covered with Cut 1 per plans. 11-04-04 Blanket re-install not completed. Nothing at edge of pavement. 11-11-04 In progress. Nothing at edge of pavement.	10-29-04	11/4	Open
W14-01	Valley View NB Ramp Initial protection needed at top of hill ramp.	11-16-04	11/19	Open
W14-02	Sta. 422 - 428R Stabilize area next to NB Ramp.	11-16-04	11/19	Open
W14-03	Sta. 428R Repair air fence.	11-16-04	11/19	Open
W14-04	Sta. 426 - 428 Stabilize Sta. 432-439, Sta. 443-450, Sta. 459-483, Sta. 632-642, Sta. 661-688 Cl.	11-16-04	11/20	Open
W14-05	Sta. 426 - 428 Stabilize Sta. 439-443, Sta. 455-459, Sta. 488-503	11-16-04	11/19	Open

11-16-04 Stabilize 10' exposed soil with a minimum slope within 20' of concrete curb.

11-16-04 Type 1 cover area with slope 1:0.5. Use 1500' of geotextile fabric reinforced with aggregate rock material. Erodex use of aggregate rock material.

11-16-04 Exposed soil with positive slope to creek at the end of ditch with the same material (slope of 2:1) placed in place of pavement. Observe within 7 days of start of work. Working for slope 1:0.5 in place area not covered with slope. Stabilize 10' concrete pavement curb with aggregate material.

11-16-04 Monitor in grade sediment trap and 2' banked ditch faces.

### VI. OFFSITE IMPACTS FROM PROJECT

1) Are there any offsite impacts?  Yes  No If yes, where?  Public Right of Way  Adjoining Property Owner  Wetlands  Creek/River  Lake/Pond  Other (please specify):

2) If answering "Yes" to the previous question, indicate the location and describe the impact:

### VII. DEFICIENCIES/ CORRECTIVE ACTIONS

Were deficiencies noted in this inspection previously listed in a monthly report?  Yes  No  
Corrective Action needed as a result of this inspection, including date to be completed:

### VIII. STORM WATER POLLUTION PREVENTION PLAN UPDATES

Y  N  1) Does the SWPPP need to be modified as a result of the inspection?  
Y  N  2) Has the SWPPP been modified since the last inspection? If so, note the date(s):

### IX. COMMENTS

Inspector: \_\_\_\_\_ Title/Qualifications: \_\_\_\_\_

## Must Define the SWPPP amendment process



11-16-04 Stabilize 10' exposed soil with a minimum slope within 20' of concrete curb.

11-16-04 Type 1 cover area with slope 1:0.5. Use 1500' of geotextile fabric reinforced with aggregate rock material. Erodex use of aggregate rock material.

11-16-04 Exposed soil with positive slope to creek at the end of ditch with the same material (slope of 2:1) placed in place of pavement. Observe within 7 days of start of work. Working for slope 1:0.5 in place area not covered with slope. Stabilize 10' concrete pavement curb with aggregate material.

11-16-04 Monitor in grade sediment trap and 2' banked ditch faces.

11-16-04 Monitor in grade sediment trap and 2' banked ditch faces.

### SWPPP Amendment for Total Valley View Road Construction

Prepared by: Dan W. Heston, CRIC #4521  
Reviewed by: Department of Transportation  
October 20, 2009

The following items were reviewed during the SWPPP inspection and found to be deficient. The SWPPP was amended to address the deficiencies. The following items were reviewed during the SWPPP inspection and found to be deficient. The SWPPP was amended to address the deficiencies.

1. Inadequate erosion control measures.
2. Inadequate sediment control measures.
3. Inadequate stormwater management measures.
4. Inadequate site access control measures.
5. Inadequate site security measures.
6. Inadequate site cleanup measures.
7. Inadequate site restoration measures.
8. Inadequate site monitoring measures.
9. Inadequate site reporting measures.
10. Inadequate site record keeping measures.



11-16-04 Stabilize 10' exposed soil with a minimum slope within 20' of concrete curb.

11-16-04 Type 1 cover area with slope 1:0.5. Use 1500' of geotextile fabric reinforced with aggregate rock material. Erodex use of aggregate rock material.

11-16-04 Exposed soil with positive slope to creek at the end of ditch with the same material (slope of 2:1) placed in place of pavement. Observe within 7 days of start of work. Working for slope 1:0.5 in place area not covered with slope. Stabilize 10' concrete pavement curb with aggregate material.

11-16-04 Monitor in grade sediment trap and 2' banked ditch faces.

## Corrective Action Plan Amendment




11-16-04 Stabilize 10' exposed soil with a minimum slope within 20' of concrete curb.

11-16-04 Type 1 cover area with slope 1:0.5. Use 1500' of geotextile fabric reinforced with aggregate rock material. Erodex use of aggregate rock material.

11-16-04 Exposed soil with positive slope to creek at the end of ditch with the same material (slope of 2:1) placed in place of pavement. Observe within 7 days of start of work. Working for slope 1:0.5 in place area not covered with slope. Stabilize 10' concrete pavement curb with aggregate material.

11-16-04 Monitor in grade sediment trap and 2' banked ditch faces.



### Amendment Process = Site Plan


S.P. 198-132, 428-91 - Division 5-27.2.8  
Site and Dewatering Plan

**Project Site West of Mississippi River**

- West Abutment**
  - Install 50' Fences before the start of the slope. 50' Fences should follow UPRR tracks 117' east of centerline.
  - Install 50' Fences along UPRR tracks inside the standard 50' Fence to protect track adjacent embankment, approximately 100'.
- Violations Areas**
  - Install the perimeter of installation of this Plan and Violations Area. You intend to protect, cover or seal the site of the work. Install a "Sheddy Wall" as well.
- Construction Staging Area**
  - Temporary Staging Area previously installed to support staging area will act as a Super Duty 50' Ca. Temporary Staging Area for the duration of the project.
  - Install concrete 50' Fences along existing chain-link fence located on the northeast portion of the site area. Install two new sections of 40' chain-link fence on the north side of the site near the existing chain-link fence where the temporary Staging Area, and the other on the south side of the existing chain-link fence a distance from existing staging area (see attached 2-D plan view).
- Temporary Enclosure**
  - Install concrete 50' Fences along existing chain-link fence located on the northeast portion of the site area. Install two new sections of 40' chain-link fence on the north side of the site near the existing chain-link fence where the temporary Staging Area, and the other on the south side of the existing chain-link fence a distance from existing staging area (see attached 2-D plan view).
- Par 4 Culmination Enclosure**
  - Dewatering will be performed with the use of 2 - 4" submersible pumps. Anticipate approximately 1000 GPM of discharge.
  - North discharge will flow through 4" flexible hose to an existing sediment pond located directly to the south of the Par 4 Culmination. Discharge will be above the sediment pond and be directed to flow through the outlet pipe to the top prior to entering pond. Flood drains directly to flow through the outlet pipe to the top prior to entering pond. Flood drains directly to flow through the outlet pipe to the top prior to entering pond. Flood drains directly to flow through the outlet pipe to the top prior to entering pond.
- Mississippi River**
  - Permissible work should not be done in Construction Staging Area when there is a potential for flooding of the Mississippi River.
  - When Emergency Shut-Off (ESOS) System will be located in Construction Staging Area. One Emergency Shut-Off (ESOS) System will be located in Staging Area off Violations Area.
  - Chain-link fence will be installed and elevated 6' above the ground surface.
  - Equipment maintenance and fueling of equipment that does not have to be performed in Construction Staging Area off Staging Area. Clean and replace that are not suitable to store the maintenance and fueling will be performed with concrete cation.
  - Request to meet with MWD to discuss location of Construction Staging Area.

**Project Site East of Mississippi River**

- East Abutment**
  - Install 50' Fences along slope before retaining wall. Install 50' Fences to 50' Fences to capture run off from erosion control and prevent block along River Bridge Access Road.
  - Provide adequate protection of location above on Site Plan.
- River Bridge Access Road**
  - Provide adequate protection of location above on Site Plan.
- Par 4 Rock Enclosure**
  - Install concrete 50' Fences along existing chain-link fence located on the northeast portion of the site area. Install two new sections of 40' chain-link fence on the north side of the site near the existing chain-link fence where the temporary Staging Area, and the other on the south side of the existing chain-link fence a distance from existing staging area (see attached 2-D plan view).
- Par 4 Culmination Enclosure**
  - Dewatering will be performed with the use of 2 - 4" submersible pumps. Anticipate approximately 1000 GPM of discharge.
  - North discharge will flow through 4" flexible hose to an existing sediment pond located directly to the south of the Par 4 Culmination. Discharge will be above the sediment pond and be directed to flow through the outlet pipe to the top prior to entering pond. Flood drains directly to flow through the outlet pipe to the top prior to entering pond. Flood drains directly to flow through the outlet pipe to the top prior to entering pond.
- Mississippi River**
  - Permissible work should not be done in Construction Staging Area when there is a potential for flooding of the Mississippi River.
  - When Emergency Shut-Off (ESOS) System will be located in Construction Staging Area. One Emergency Shut-Off (ESOS) System will be located in Staging Area off Violations Area.
  - Chain-link fence will be installed and elevated 6' above the ground surface.
  - Equipment maintenance and fueling of equipment that does not have to be performed in Construction Staging Area off Staging Area. Clean and replace that are not suitable to store the maintenance and fueling will be performed with concrete cation.
  - Request to meet with MWD to discuss location of Construction Staging Area.



### TH100 wetland bridge (Ames GeoWood Road)

**Temporary Access Road for Bridge 2104**

**Violations Area Note**

Per 40' Fences or 50' Fences to be installed in Construction Staging Area when there is a potential for flooding of the Mississippi River.

When Emergency Shut-Off (ESOS) System will be located in Construction Staging Area. One Emergency Shut-Off (ESOS) System will be located in Staging Area off Violations Area.

Chain-link fence will be installed and elevated 6' above the ground surface.


Equipment maintenance and fueling of equipment that does not have to be performed in Construction Staging Area off Staging Area. Clean and replace that are not suitable to store the maintenance and fueling will be performed with concrete cation.



Request to meet with MWD to discuss location of Construction Staging Area.

**AMES CONSTRUCTION, INC.**  
2005 AMT DRIVE  
BARNESVILLE, MO 65214

BRIDGE #27A74 HIGHWAY 100  
WORK ROAD DETAILS

DATE: N.T.S.  
REV: 4-2-2011  
APPROVED BY: [Signature]  
DESIGNER: [Signature]





### Project Review 'You Make the Call'

- Perimeter defense
- Trackout management
- Exposed soil stabilization
- Conveyance system stabilization
- Inlet controls
- Sediment trap/basin management
- Dewatering protocols
- Good housekeeping

